Installation Guide

IMPORTANT: The TAC2C has a Ringer Equivalence Number (REN) of 5 with or without a TELCO line.

Introduction

CAUTION

DO NOT run data wires and HIGH VOLTAGE wires in the same conduit. The HIGH VOLTAGE wires may interfere with the data wires and cause the unit to malfunction.

To AVOID damaging gas, power or other underground utility lines, contact underground utility locating companies BEFORE digging. To prevent damage to the unit:

- Use the new 16 Vdc transformer ONLY.
- Use dedicated 110 Vac outlet ONLY.

CARTON INVENTORY

Hardware Bag

Complete with: Hex Head Tamper Resistant Screws (4), Hex Tool (1), and Ground Lug (1)

Faceplate with Processor Board (1)

16 Volt DC 2.5 Amp Transformer (UL Listed) (1)

Install and Programming Guide (1)

Labels (9)


SPECIFICATIONS


Power Supply: 16 Vdc 2.5 Amp


The 110 Vac outlet must be dedicated to the unit only. This outlet should be wired back to its own 10 Amp minimum circuit breaker. This will prevent two problems:


- Other equipment cannot introduce spikes, noise, surges, or dips into the power circuit.
- The unit's operation will not be affected if any other equipment develops a short circuit across the power line.

Dimensions: 9.72" x 6.22" (W x H)













LiftMaster TAC2C


TAC1 RETROFIT KIT FOR CROWN JEWEL SYSTEMS














SET THE MASTER CODE Once power is applied, the unit will begin to "click" to indicate that it is powered, and is waiting to be programmed for the unit's Master Code. The Master Code is used to unlock the programming functions of the unit. The Master Code should not be distributed as a User Code. on the unit's keypad. **2** Enter 4-digit Master Code. Example: 1234. "BEEP" "BEEP" Write down the Master Code and store in a secure location.

Testing

TEST GATE / DOOR RELAYS

Test Relay 1

1 Enter 4 digit Master Code.



2 Press 1 to test Relay 1.



Test Relay 2

1 Enter 4 digit Master Code.









? Press 2 to test Relay 2.



TEST THE TELEPHONE CONNECTIONS

- 1 Place a telephone call from the resident's telephone to verify the unit is operating properly, then hang up the phone.
- Press the "Call" button on the unit's keypad. The telephone in the residence should ring.



3 To test Relay 1 have someone answer the telephone and enter "*9" (Star + 9) to activate Relay 1. The unit will disconnect the call as soon as the relay is activated. To test Relay 2 have someone answer the telephone and enter "*5" (Star + 5). Relay 2 should activate. The unit will disconnect the call as soon as the relay is activated.

For complete programming information refer to the Programming Guide.